

WILDERNESS CABINS CONSTRUCTION INFORMATION

- Detachable hitch
- 10" I-beam frame w/tandem axles
- 2x6 floor joist 16" o.c.
- Double 2x6 perimeter floor joist
- 3/4" t&g osb floor decking
- 2x4 exterior walls 16" o.c.
- Custom built 2x6 rafters
- Moisture barrier vapor wrap
- Double studs every 4'-0"
- Double 2x6 headers over windows and doors
- Triple studs around windows & doors
- Thermo pane windows and doors
- Pex water lines
- Cut off valves through out
- Electrical outlets and light fixtures
- Custom hand crafted cyprus cabinets
- Rolled countertops & rolled backsplashes
- Foam seal on all exterior plugs and switches
- Foam seal on every exterior stud
- 6 hurricane straps (3 each side)
- R-13 insulation in walls
- R-22 insulation in floor
- R-19 insulation in ceiling
- LP smart side siding
- 12" overhangs front & rear
- 100 amp electrical service
- NEC approved electrical wiring
- 7/16" osb/tech shield radiant barrier on roof
- 15# felt paper

WILDERNESS CABINS CONSTRUCTION INFORMATION

- Colored metal roof (29 gauge)
- Vaulted ceiling throughout (excluding loft area)
- TRA coded and inspected

Important Note: Due to product improvement or structural design Wilderness Cabins reserves the right to change specifications without prior notification or obligation. We reserve the right to change, add or delete tiny house and tiny cabin features and specs at any time and without further notice. Some features will automatically change with our cabins that are built to International Building Codes (without wheels.) Questions of any kind, please inquire directly with us. Thank you.